


NIMSIRI CO. LTD.

Airflow and Acoustic Research and Development Study of various Air Outlets



Report No. 30B-09-0035-TRP-400414-2

Vipac Engineers & Scientists Ltd

Melbourne, VIC

July 2009



**WORLD RECOGNISED
ACCREDITATION**



ViPAC

This document is issued in accordance with NATA's accreditation requirements

DOCUMENT CONTROL

Airflow and Acoustic Research and Development Study of various Air Outlets

REPORT NO:

30B-09-0011-TRP-400414-2

PREPARED FOR:

NIMSIRI Co Ltd
249 Moo9 Suksawad Rd
Bangpakok Radburana
BANGKOK Thailand 10140

Contact: Chotipat Yamchai-Anan

Phone: (+66) 2428 6334

Fax : (+66) 2428 6131

LIBRARY CODE:
PREPARED BY:

Vipac Engineers & Scientists Ltd
279 Normanby Road
Port Melbourne VIC 3207
AUSTRALIA

Email: melbourne@vipac.com.au

Phone: 61 3 9647 9700

Fax : 61 3 9646 4370

AUTHOR:

Zarko Drinic
Senior Project Engineer

Date: 31/07/09

REVIEWED BY:

Michael Smith
N.A.T.A Signatory

Date:

31/7/09

REVISION HISTORY:

| Revision No. | Date Issued | Reason/Comments |
|--------------|-------------|-----------------|
| 02 | July 2009 | Additional Data |

DISTRIBUTION:

| Copy No. | Issue No. | Location |
|----------|-----------|-------------------------|
| 1 | 2 | Client |
| 2 | 0 | Project File |
| 3 | 0 | VIPAC Melbourne Library |

KEYWORDS: Diffuser, Noise

NOTE: This is a controlled document within the document control system. If revised, it must be marked SUPERSEDED and returned to the Vipac QA Representative.



TABLE OF CONTENTS

| | |
|------------------------------------------------|----|
| 1. INTRODUCTION | 4 |
| 2. UNITS UNDER TEST | 4 |
| 3. TEST CONDITION AND APPLICABLE STANDARD..... | 7 |
| 4. TEST SET UP AND PROCEDURES | 7 |
| 5. INSTRUMENTATION | 10 |
| 6. ORDERS OF ACCURACY | 10 |
| 7. RESULTS..... | 11 |





Figure 2: Test Unit No.2 – Linear Slot Diffuser



Figure 3: Test Unit No.3 – Linear Bar Grille



Figure 2: Test Unit No.4 – Square Ceiling Diffuser



Figure 5: Test Unit No.5 – Return Air Grille



3. TEST CONDITIONS AND APPLICABLE STANDARDS

The unit was tested at a range of flow conditions, as shown on the Test Certificate.

The test set up was in general accordance with Air Diffusion Council (USA) Equipment Test Code 1062: GRD-84. Measurements were taken in general accordance with the following standards:

ACOUSTICS

Australian Standard 1217.2-1985. "Acoustic - Determination of Sound Power Levels of Noise Sources Part 2 - Precision Methods for Broad-Band Sources in Reverberation Rooms".

AIRFLOW

Air Diffusion Council (USA) Equipment Test Code 1062: GRD-84.

THROW & STATIC PRESSURE DROP

Air Diffusion Council (USA) Equipment Test Code 1062: GRD-84.

4. TEST SET UP AND PROCEDURE

Vipac's Reverberation Test Room has a volume of 170m³ has been qualified in accordance with the procedures in AS 1217.2 - 1985 for determination of sound power in octave bands with Centre Frequencies from 125 Hz to 8000 Hz.

The unit under test was set up in the Air Distribution (Reverberation) Test Chamber and connected to a quiet air supply.

The unit was supplied with ambient temperature air at the specified airflow. The environmental test conditions in the reverberation chamber varied within the following ranges:

| | | |
|----------------------|---------------|----------------|
| Test Air Temperature | 16 degrees C | ± 2.0 degree C |
| Room Air Temperature | 18 degrees C | ± 2.0 degree C |
| Barometric Pressure | 1050 millibar | ± 5 millibar |
| Relative Humidity | 55 | ± 10% |

Following calibration checks, sound pressure levels were measured and converted to sound power levels using the comparison method of AS1217.2 - 1985 (ie. using a reference sound source of known Sound Power to determine room correction).

Airflow rates were measured using Ø 150 mm orifice plate. Static pressure drop was recorded using a (Static Pressure) probe and an inclined manometer. Throw was measured using a hotwire type anemometer. Figure 6 shows the test set up (Ceiling Installation). Figure 7 shows the test set up (Wall Installation).




Figure 6: Test Set-up (Ceiling Installation)




Figure 7: Test Set-up (Wall Installation)





5. INSTRUMENTATION

| INSTRUMENT | MAKE & MODEL | CALIBRATION | | SERIAL NO. |
|---------------------|-------------------|----------------------------|------------|---------------|
| | | BY | DATE | |
| Sound Level Meter | ONO SOKKI LA-5570 | Vipac | 09/09/2008 | 47958 / 20627 |
| Microphone | MI-3310 | Vipac | 09/09/2008 | 21367 |
| Acoustic Calibrator | B&K 4230 | Vipac | 30/01/2008 | 860700 |
| Manometers (2) | Incline Manometer | Australian Pressure Lab | 28/07/2008 | PM6 - 168 |
| | EMA 200 | | 09/09/08 | KH320630 |
| Orifice Plates | Vipac | Vipac | May 2001 | - |
| Hotwire Anemometer | TSI 9545-A | TSI | 01/04/2008 | 9545A0813010 |

6. ORDERS OF ACCURACY

| <u>Sound Pressure Level:</u> | Octave Band Centre Frequency (Hz) | Standard Deviation (1) (dB) |
|------------------------------|--------------------------------------|--------------------------------|
| | 125 | ± 3.0 |
| | 250 | ± 2.0 |
| | 500 to 4000 | ± 1.5 |
| | 8000 | ± 3.0 |

Pressure Drop: $\pm 5\%$ or 0.5 Pa whichever is greater

Airflow: $\pm 5\%$ or 10 l/s whichever is greater





7. RESULTS

The results obtained are shown in the attached Test Certificates.

Report Prepared by:
VIPAC ENGINEERS AND SCIENTISTS LTD.

.....
ZARKO DRINIC
SENIOR PROJECT ENGINEER

.....
MICHAEL SMITH
N.A.T.A. SIGNATORY



**TEST CERTIFICATE No.1****ACOUSTIC AND AIRFLOW PERFORMANCE TESTS OF VARIOUS OUTLETS**

SUPPLIED BY: NIMSIRI CO LTD
TESTED BY: VIPAC ENGINEERS & SCIENTISTS LTD
TEST DATE: MARCH 2009
CLIENT: NIMSIRI CO LTD
UNIT: Double Deflection Grille
SIZE: 600 mm x 150 mm

| TEST CONDITIONS | | | | SOUND POWER LEVEL, dB re 1E-12 W | | | | | | |
|-----------------|------------|----------|----|-----------------------------------|------|------|------|------|-------|-------|
| | | | | OCTAVE BAND CENTRE FREQUENCY (Hz) | | | | | | |
| Qs (L/s) | Ps (Pa) | T (m) | NC | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| 234 | 11 | 12.6* | 22 | <46.6 | 41.9 | 33.0 | 26.4 | 21.2 | <15.4 | <11.0 |
| 264 | 14 | 13.5* | 25 | 48.1 | 43.9 | 36.7 | 30.0 | 24.5 | 17.3 | <11.9 |
| 320 | 21 | 15.0* | 31 | 50.2 | 47.8 | 41.9 | 36.1 | 30.9 | 23.8 | 15.1 |
| 362 | 28 | 15.6* | 34 | 52.9 | 50.7 | 44.9 | 39.7 | 34.7 | 28.5 | 18.6 |
| 402 | 35 | 16.2* | 38 | 58.7 | 54.1 | 48.7 | 43.6 | 39.2 | 33.6 | 24.8 |

LEGEND

- Qs - Primary Air Flow Rate (L/s)
 Ps - Supply Static Pressure (Pa)
 < - Insufficient margin above background noise to allow accurate determination
 > - Length of throw greater than that able to be measured
 NC - Noise Criterion based upon room absorption of 10 dB
 T - Horizontal Throw in meters at terminal velocity of 0.25m/s
 * - Extrapolated values (excluded from NATA accreditation)


 Zarko Drinic
 SENIOR PROJECT ENGINEER


 Michael Smith
 N.A.T.A. SIGNATORY



**TEST CERTIFICATE No.2****ACOUSTIC AND AIRFLOW PERFORMANCE TESTS OF VARIOUS OUTLETS**

SUPPLIED BY: NIMSIRI CO LTD
TESTED BY: VIPAC ENGINEERS & SCIENTISTS LTD
TEST DATE: MARCH 2009
CLIENT: NIMSIRI CO LTD
UNIT: Linear Slot Diffuser
SIZE: 800 mm x 100 mm

| TEST CONDITIONS | | | | SOUND POWER LEVEL, dB re 1E-12 W OCTAVE BAND CENTRE FREQUENCY (Hz) | | | | | | |
|-----------------|------------|----------|----|-----------------------------------------------------------------------|------|------|------|------|-------|-------|
| Qs (L/s) | Ps (Pa) | T (m) | NC | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| 195 | 8 | 11.0* | 21 | <47.8 | 41.7 | 31.6 | 23.4 | 17.8 | <12.7 | <10.6 |
| 220 | 11 | 12.2* | 26 | 48.6 | 43.4 | 37.5 | 26.3 | 21.7 | 15.0 | <10.7 |
| 252 | 15 | 13.3* | 30 | 50.4 | 46.5 | 41.6 | 32.1 | 29.4 | 23.2 | <11.1 |
| 287 | 21 | 13.9* | 32 | 52.0 | 49.6 | 43.2 | 35.2 | 34.4 | 29.5 | 13.2 |
| 345 | 33 | 15.3* | 38 | 58.1 | 54.7 | 48.7 | 42.6 | 42.5 | 39.5 | 22.6 |

LEGEND

- Qs - Primary Air Flow Rate (L/s)
Ps - Supply Static Pressure (Pa)
< - Insufficient margin above background noise to allow accurate determination
> - Length of throw greater than that able to be measured
NC - Noise Criterion based upon room absorption of 10 dB
T - Horizontal Throw in meters at terminal velocity of 0.25m/s
* - Extrapolated values (excluded from NATA accreditation)


Zarko Drinic
SENOIR PROJECT ENGINEER


Michael Smith
N.A.T.A. SIGNATORY

Ref: 30B-09-0011-400414-2

July 2009



NATA Accredited
Laboratory
Numbers: 1163 & 1506

This document is issued in accordance with NATA's accreditation requirements. Accredited for compliance with ISO / IEC 17025. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian / national standards.

**TEST CERTIFICATE No.3****ACOUSTIC AND AIRFLOW PERFORMANCE TESTS OF VARIOUS OUTLETS**

SUPPLIED BY: NIMSIRI CO LTD
TESTED BY: VIPAC ENGINEERS & SCIENTISTS LTD
TEST DATE: MARCH 2009
CLIENT: NIMSIRI CO LTD
UNIT: Linear Bar Grille
SIZE: 600 mm x 150 mm

| TEST CONDITIONS | | | | SOUND POWER LEVEL, dB re 1E-12 W OCTAVE BAND CENTRE FREQUENCY (Hz) | | | | | | |
|-----------------|------------|----------|----|-----------------------------------------------------------------------|------|------|------|-------|-------|-------|
| Qs (L/s) | Ps (Pa) | T (m) | NC | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| 211 | 9 | 11.4* | 21 | <46.6 | 41.4 | 32.1 | 24.8 | <20.1 | <14.7 | <10.9 |
| 248 | 12 | 13.2* | 25 | <47.1 | 42.6 | 36.5 | 28.2 | 22.8 | 15.9 | <11.0 |
| 299 | 18 | 14.4* | 30 | 48.6 | 46.1 | 41.2 | 35.0 | 29.4 | 20.8 | <12.1 |
| 357 | 25 | 15.6* | 36 | 54.4 | 52.2 | 46.7 | 42.3 | 36.5 | 29.9 | 19.3 |
| 413 | 34 | 16.8* | 41 | 59.8 | 55.8 | 49.9 | 46.8 | 41.9 | 36.2 | 26.4 |

LEGEND

- Qs - Primary Air Flow Rate (L/s)
Ps - Supply Static Pressure (Pa)
< - Insufficient margin above background noise to allow accurate determination
> - Length of throw greater than that able to be measured
NC - Noise Criterion based upon room absorption of 10 dB
T - Horizontal Throw in meters at terminal velocity of 0.25m/s
* - Extrapolated values (excluded from NATA accreditation)


Zarko Drinic
SENOIR PROJECT ENGINEER


Michael Smith
N.A.T.A. SIGNATORY

Ref: 30B-09-0011-400414-2

July 2009



NATA Accredited
Laboratory
Numbers: 1163 & 1506

This document is issued in accordance with NATA's accreditation requirements. Accredited for compliance with ISO / IEC 17025. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian / national standards.

TEST CERTIFICATE No.4

ACOUSTIC AND AIRFLOW PERFORMANCE TESTS OF VARIOUS OUTLETS

SUPPLIED BY: NIMSIRI CO LTD
TESTED BY: VIPAC ENGINEERS & SCIENTISTS LTD
TEST DATE: MARCH 2009
CLIENT: NIMSIRI CO LTD
UNIT: Square Ceiling Diffuser
SIZE: 300 mm x 300 mm

| TEST CONDITIONS | | | | SOUND POWER LEVEL, dB re 1E-12 W OCTAVE BAND CENTRE FREQUENCY (Hz) | | | | | | |
|-----------------|------------|----------|----|-----------------------------------------------------------------------|------|------|------|-------|-------|-------|
| Qs (L/s) | Ps (Pa) | T (m) | NC | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| 193 | 8 | 10.4* | 22 | <47.3 | 42.5 | 33.8 | 25.0 | <19.0 | <13.1 | <10.5 |
| 222 | 11 | 10.8* | 26 | <47.5 | 43.3 | 37.5 | 28.3 | 23.2 | 17.1 | <10.8 |
| 280 | 19 | 12.2* | 31 | 49.1 | 45.9 | 42.2 | 36.0 | 28.7 | 20.3 | <11.6 |
| 337 | 27 | 13.5* | 36 | 52.1 | 50.7 | 46.8 | 42.3 | 36.1 | 29.0 | 17.0 |
| 390 | 38 | 14.4* | 40 | 56.8 | 54.8 | 50.2 | 46.5 | 41.8 | 35.8 | 24.9 |

LEGEND

- Qs - Primary Air Flow Rate (L/s)
 Ps - Supply Static Pressure (Pa)
 < - Insufficient margin above background noise to allow accurate determination
 > - Length of throw greater than that able to be measured
 NC - Noise Criterion based upon room absorption of 10 dB
 T - Horizontal Throw in meters at terminal velocity of 0.25m/s
 * - Extrapolated values (excluded from NATA accreditation)


 Zarko Drinic
 SENIOR PROJECT ENGINEER


 Michael Smith
 N.A.T.A. SIGNATORY

Ref: 30B-09-0011-400414-2

July 2009



NATA Accredited
 Laboratory
 Numbers: 1163 & 1506

This document is issued in accordance with NATA's accreditation requirements. Accredited for compliance with ISO / IEC 17025. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian / national standards.

TEST CERTIFICATE No.5

ACOUSTIC AND AIRFLOW PERFORMANCE TESTS OF VARIOUS OUTLETS

SUPPLIED BY: NIMSIRI CO LTD
TESTED BY: VIPAC ENGINEERS & SCIENTISTS LTD
TEST DATE: MARCH 2009
CLIENT: NIMSIRI CO LTD
UNIT: Return Air Grille
SIZE: 600 mm x 400 mm

| TEST CONDITIONS | | | SOUND POWER LEVEL, dB re 1E-12 W OCTAVE BAND CENTRE FREQUENCY (Hz) | | | | | | |
|-----------------|------------|----|-----------------------------------------------------------------------|------|------|------|------|-------|-------|
| Qs (L/s) | Ps (Pa) | NC | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| 206 | 3 | 19 | <45.9 | 39.9 | 29.4 | 22.7 | 18.5 | <15.7 | <15.4 |
| 268 | 5 | 23 | 47.7 | 42.8 | 34.2 | 28.5 | 24.0 | 17.9 | <15.9 |
| 358 | 7 | 30 | 53.7 | 48.7 | 41.1 | 35.3 | 32.0 | 25.7 | 19.1 |
| 413 | 10 | 35 | 57.9 | 52.3 | 45.7 | 40.1 | 36.7 | 31.2 | 25.6 |
| 476 | 13 | 39 | 61.4 | 56.4 | 49.6 | 43.8 | 40.7 | 35.2 | 28.9 |

LEGEND

Qs - Primary Air Flow Rate (L/s)
 Ps - Supply Static Pressure (Pa)
 < - Insufficient margin above background noise to allow accurate determination
 NC - Noise Criterion based upon room absorption of 10 dB


 Zarko Drinic
 SENOIR PROJECT ENGINEER


 Michael Smith
 N.A.T.A. SIGNATORY

Ref: 30B-09-0011-400414-2

July 2009



NATA Accredited
 Laboratory
 Numbers: 1163 & 1506

This document is issued in accordance with NATA's accreditation requirements. Accredited for compliance with ISO / IEC 17025. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian / national standards.